



INSERT MAIN SITE PHOTO (PM to do)

**Hotel Name**

Surveyor  
23 October 2026

## Change Control

---

| Date | Version | Reason for change |
|------|---------|-------------------|
|      |         |                   |
|      |         |                   |
|      |         |                   |
|      |         |                   |
|      |         |                   |

## INTRODUCTION

---

|                   |  |
|-------------------|--|
| Site Name         |  |
| Site Address      |  |
| Contact Name      |  |
| Contact Position  |  |
| Contact Telephone |  |

| Site Survey Requirements                                                                                                                                                                                                                                                                                                                                                                                                                     |                                            |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------|
| Type of survey required – Full                                                                                                                                                                                                                                                                                                                                                                                                               | All areas of the hotel. In-room 1:1 Layout |
| Note areas where service is excluded:                                                                                                                                                                                                                                                                                                                                                                                                        | Yes                                        |
| <p>Ideally all areas of the hotel, including back of house are in scope for this survey. The requirement is for one MR36H access point to be installed in each guest room typically behind the TV, and additional guest corridor, public area and BoH APs to allow for services such as VoIP staff handsets. The hotel has confirmed that the following areas are out of scope, stairwells, lifts, staff changing rooms, public toilets.</p> |                                            |

| Survey Methodology                                                                                                                                                                                                                                                                                                                            |                   |                  |                        |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------|------------------|------------------------|
| Equipment                                                                                                                                                                                                                                                                                                                                     |                   |                  |                        |
| Laptop OS:                                                                                                                                                                                                                                                                                                                                    | macOS Sonoma 14.0 | Survey software: | Ekahau AI Pro 11.4.1.1 |
| USB adapter:                                                                                                                                                                                                                                                                                                                                  | Sidekick 2        | Access point:    | MR36 & MR36H           |
| <p>The survey was conducted using the 'AP on a Stick' method, on the basis of an in-room solution of one AP per room located behind the TV, with additional APs installed in the corridor/guest areas to provide 100% coverage.</p> <p>The survey was conducted to ensure that there was a minimum coverage level of -65dBm in all areas.</p> |                   |                  |                        |

| Site Details                                                                                                       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
|--------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Describe in full the number of buildings, floors, meeting rooms and location of bedrooms, etc.                     | There is only one building to consider for this network. It consists of 6 floors. There are 5 different room types, Queen Standard, 2 Single Standard, Standard, King Premium and Premium. There are 165 rooms in total across 5 of the 6 floors. There is a large restaurant area and bar on the ground floor with 2 private dining rooms and a separate club lounge there are also 10 function/meeting rooms with a large pre meeting area and separate bar. |
| Describe the architectural structure of the buildings (i.e. stud walls, very thick walls, Grade I/II listed, etc.) | White external insulated render to hotel upper floors to rear elevation Rain-screen cladding system, with varying colours of light grey /silver and gold to hotel upper floors to front elevation. Hotel ground floor entrance area has a mix of curtain-walling (Ppc aluminium double glazed curtain walling system, Bedroom windows: Grey double-glazed windows. Internal structure is breeze block and plaster board.                                       |
| Do bedrooms have available data ports (yes/no)<br>If yes:<br>1) Located where?<br>2) In use?                       | Yes<br><br>Behind TV and in desk. It was established that there is only one port behind the TV in the bedrooms which is used for IPTV and in desk was a single port, all were cabled although note that the wired desk connection gave no IP address when connected.                                                                                                                                                                                           |

| Meeting Rooms                                                                                                                  |               |        |                               |            |                   |
|--------------------------------------------------------------------------------------------------------------------------------|---------------|--------|-------------------------------|------------|-------------------|
| No                                                                                                                             | MEETING ROOMS | FLOOR  | DATA SOCKETS PRESENT (YES/NO) | PORT LABEL | CABLED TO MDF/IDF |
| 1                                                                                                                              | One - 80      | Ground | Yes                           |            | IDFG              |
| 2                                                                                                                              | Two – 200     | Ground | Yes                           |            | IDFG              |
| 3                                                                                                                              | Three – 30    | Ground | Yes                           |            | IDFG              |
| 4                                                                                                                              | Four – 40     | Ground | Yes                           |            | IDFG              |
| 5                                                                                                                              | Five – 40     | Ground | Yes                           |            | IDFG              |
| 6                                                                                                                              | Six – 40      | Ground | Yes                           |            | IDFG              |
| 7                                                                                                                              | Seven – 40    | Ground | Yes                           |            | IDFG              |
| 8                                                                                                                              | Eight – 18    | Ground | Yes                           |            | IDFG              |
| 9                                                                                                                              | Nine – 8      | Ground | Yes                           |            | IDFG              |
| 10                                                                                                                             | Ten– 12       | Ground | Yes                           |            | IDFG              |
| <b>Comments: Rooms 1 &amp; 2 combine for 280 – 3, 4 &amp; 5 combine for 110 – 6 &amp; 7 combine for 80</b>                     |               |        |                               |            |                   |
| Site confirmed that the do not use the floor or wall outlets for data connections, some ports are used for IPTV when required. |               |        |                               |            |                   |

| PMS                                                                             |     |
|---------------------------------------------------------------------------------|-----|
| PMS INSTALLED                                                                   | N/A |
| PMS LOCATION                                                                    | N/A |
| INTERFACE PRESENT                                                               | N/A |
| <b>Comments:</b>                                                                |     |
| PMS is not integrated into the Wi-Fi as Wi-Fi is free with no landing page etc. |     |

| Third Party Services                                                                                       |                               |
|------------------------------------------------------------------------------------------------------------|-------------------------------|
| Number of third-party services to be added to the network (i.e. will require switch ports or wifi support) |                               |
| SERVICE NAME                                                                                               | WIRELESS/WIRED/Not applicable |
| Smart TV                                                                                                   | Wired                         |
| In room wired 1 port per room                                                                              | Wired                         |

## SITE LAYOUT

| Floors       | Number of rooms | Room numbers              |
|--------------|-----------------|---------------------------|
| Ground Floor | 0               |                           |
| First Floor  | 33              | 101 – 112, 114, 116 - 135 |
| Second Floor | 33              | 201 – 212, 214, 216 – 235 |
| Third Floor  | 33              | 301 – 312, 314, 316 – 335 |
| Fourth Floor | 33              | 401 – 412, 414, 416 - 435 |
| Fifth Floor  | 33              | 501 – 512, 514, 516 - 535 |

**COMMENTS:** In the Club Lounge there is one PC connected to outlet A1-005 and in reception there is a PC connected to outlet A-208 and a printer to A-209 both will require a wired connection for LAN/internet access by guests.


## EXISTING NETWORK ARCHITECTURE

| Wireless access points |                                 |     |                    |
|------------------------|---------------------------------|-----|--------------------|
| MAKE                   | MODEL                           | QTY | REUSEABLE FOR EDGE |
| Ruckus                 | R300                            | 1   |                    |
| Cisco                  | Aironet 1142                    | 1   |                    |
| Cisco                  | AIR-CAP1602I-E-K9 Aironet 1602i | 59  |                    |
| Network Switches       |                                 |     |                    |
| MAKE                   | MODEL                           | QTY | REUSEABLE FOR EDGE |
| HP                     | 2615-8                          | 7   |                    |
| HP                     | 2620-24                         | 8   |                    |
| HP                     | 2620-48                         | 7   |                    |
| HP                     | E5406                           | 1   |                    |
|                        |                                 |     |                    |
|                        |                                 |     |                    |
| Firewall               |                                 |     |                    |
| MAKE                   | MODEL                           | QTY | REUSEABLE FOR EDGE |
| Cisco                  | ASA                             | 1   | -                  |
| Other network hardware |                                 |     |                    |
| Nomadix                | EG 6000 Access Gateway          | 1   |                    |

**COMMENTS:**

## EXISTING/PROPOSED CABINETS

| Main Distribution Frame (MDF)                                  |                                             |
|----------------------------------------------------------------|---------------------------------------------|
| DESCRIPTION                                                    | 42 U 800 x 800                              |
| LOCATION                                                       | Comms room ground floor                     |
| CONNECTED TO WHICH OTHER CABINETS                              | All IDF's                                   |
| UPLINK CABLE (COPPER/FIBRE)                                    | Copper (Fibre is available)                 |
| DESTINATION OF UPLINK(S)                                       | 3 copper links to each IDF                  |
| UPLINK CABLE INTERFACE (RJ45/LC/SC/ST/Single-mode, Multi-mode) | RJ45 (OM3 Multimode LC Duplex is available) |



| Intermediate Distribution Frame (IDFG)                         |                                             |
|----------------------------------------------------------------|---------------------------------------------|
| DESCRIPTION                                                    | 42 U 800 x 800 serves conferencing area     |
| LOCATION                                                       | Door next to meeting room 5                 |
| CONNECTED TO WHICH OTHER CABINETS                              | MDF                                         |
| UPLINK CABLE (COPPER/FIBRE)                                    | Copper (Fibre is available)                 |
| DESTINATION OF UPLINK(S)                                       | 3 copper links to MDF                       |
| UPLINK CABLE INTERFACE (RJ45/LC/SC/ST/Single-mode, Multi-mode) | RJ45 (OM3 Multimode LC Duplex is available) |




| Intermediate Distribution Frame (IDF1)                         |                                             |
|----------------------------------------------------------------|---------------------------------------------|
| DESCRIPTION                                                    | 18U 600 x 600 serves 1 <sup>st</sup> floor  |
| LOCATION                                                       | Riser next to lift lobby                    |
| CONNECTED TO WHICH OTHER CABINETS                              | MDF                                         |
| UPLINK CABLE (COPPER/FIBRE)                                    | Copper (Fibre is available)                 |
| DESTINATION OF UPLINK(S)                                       | 3 copper links to MDF                       |
| UPLINK CABLE INTERFACE (RJ45/LC/SC/ST/Single-mode, Multi-mode) | RJ45 (OM3 Multimode LC Duplex is available) |




| Intermediate Distribution Frame (IDF2)                         |                                             |
|----------------------------------------------------------------|---------------------------------------------|
| DESCRIPTION                                                    | 18U 600 x 600 serves 2 <sup>nd</sup> floor  |
| LOCATION                                                       | Riser next to lift lobby                    |
| CONNECTED TO WHICH OTHER CABINETS                              | MDF                                         |
| UPLINK CABLE (COPPER/FIBRE)                                    | Copper (Fibre is available)                 |
| DESTINATION OF UPLINK(S)                                       | 3 copper links to MDF                       |
| UPLINK CABLE INTERFACE (RJ45/LC/SC/ST/Single-mode, Multi-mode) | RJ45 (OM3 Multimode LC Duplex is available) |



| Intermediate Distribution Frame (IDF3)                         |                                             |
|----------------------------------------------------------------|---------------------------------------------|
| DESCRIPTION                                                    | 18U 600 x 600 serves 3 <sup>rd</sup> floor  |
| LOCATION                                                       | Riser next to lift lobby                    |
| CONNECTED TO WHICH OTHER CABINETS                              | MDF                                         |
| UPLINK CABLE (COPPER/FIBRE)                                    | Copper (Fibre is available)                 |
| DESTINATION OF UPLINK(S)                                       | 3 copper links to MDF                       |
| UPLINK CABLE INTERFACE (RJ45/LC/SC/ST/Single-mode, Multi-mode) | RJ45 (OM3 Multimode LC Duplex is available) |



| Intermediate Distribution Frame (IDF4)                         |                                             |
|----------------------------------------------------------------|---------------------------------------------|
| DESCRIPTION                                                    | 18U 600 x 600 serves 4 <sup>th</sup> floor  |
| LOCATION                                                       | Riser next to lift lobby                    |
| CONNECTED TO WHICH OTHER CABINETS                              | MDF                                         |
| UPLINK CABLE (COPPER/FIBRE)                                    | Copper (Fibre is available)                 |
| DESTINATION OF UPLINK(S)                                       | 3 copper links to MDF                       |
| UPLINK CABLE INTERFACE (RJ45/LC/SC/ST/Single-mode, Multi-mode) | RJ45 (OM3 Multimode LC Duplex is available) |



| Intermediate Distribution Frame (IDF5)                         |                                             |
|----------------------------------------------------------------|---------------------------------------------|
| DESCRIPTION                                                    | 18U 600 x 600 serves 5 <sup>th</sup> floor  |
| LOCATION                                                       | Riser next to lift lobby                    |
| CONNECTED TO WHICH OTHER CABINETS                              | MDF                                         |
| UPLINK CABLE (COPPER/FIBRE)                                    | Copper (Fibre is available)                 |
| DESTINATION OF UPLINK(S)                                       | 3 copper links to MDF                       |
| UPLINK CABLE INTERFACE (RJ45/LC/SC/ST/Single-mode, Multi-mode) | RJ45 (OM3 Multimode LC Duplex is available) |



#### **COMMENTS**

IDF on every floor 1 - 5 and conference area, all connected down to main MDF, currently using 3 copper connections per IDF, fibre is available but not tested during survey. Blue cables for analogue voice, white cables for AP and in room wired, black cables for IPTV.

## HEATMAPS – PROPOSED NETWORK TEST SURVEY LOCATIONS

---

| Access point placement areas                                         |                                                                                                                                                              |
|----------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------|
| LIST AREAS WHERE YOU HAVE PLACED ACCESS POINTS FOR TEST SURVEY BELOW |                                                                                                                                                              |
| Property area                                                        | Specific location                                                                                                                                            |
| Ground floor                                                         | Existing AP Locations to cover all Public and BoH areas, additional areas in conference due to poor coverage (customer complaints confirmed by maintenance). |
| First floor                                                          | Behind TV in each room, in riser near room 134, 127, IDF, 108, Housekeeping, Stair Lobby at each end of corridor.                                            |
| Second floor                                                         | Not covered in survey.                                                                                                                                       |
| Third floor                                                          | Behind TV in each room, in riser near room 334, 327, IDF, 308, Housekeeping, Stair Lobby at each end of corridor.                                            |
| Fourth floor                                                         | Not covered in survey.                                                                                                                                       |
| Fifth floor                                                          | Behind TV in each room, in riser near room 534, 527, IDF, 508, Maintenance room, Stair Lobby at each end of corridor.                                        |

## RECOMMENDATIONS

---

Based on the survey results there will be coverage in all bedrooms and required areas.

| Wireless access point recommendation summary |             |
|----------------------------------------------|-------------|
| AREA                                         | MODEL       |
| Bedrooms                                     | MR36H       |
| Lobbies and Corridors                        | MR36        |
| Restaurant and Meeting Area(s)               | MR36 & MR46 |
| Office Area                                  | MR36        |
| Other Areas                                  | MR36        |

**COMMENTS:** There is a single UTP outlet installed behind each TV location. This is where the Meraki MR36H access point will be installed. The ground floor APs should be run to the MDF and the conference AP's to the ground floor IDF in the conferencing area.

## SUMMARY OF PROPOSED NEW HARDWARE

---

| BOM for site              |     |
|---------------------------|-----|
| HARDWARE LIST             | QTY |
| Core Switch               | 1   |
| Remote Switch             | 11  |
| Meraki MR36 Access Point  | 45  |
| Meraki MR36H Access Point | 165 |
| Meraki MR46 Access Point  | 2   |

## CABLING REQUIREMENTS

---

| Location     | Existing Cables | New Cables |
|--------------|-----------------|------------|
| Ground Floor | 11              | 9          |
| First floor  | 40              | 0          |
| Second Floor | 37              | 1          |
| Third Floor  | 37              | 1          |
| Fourth Floor | 37              | 1          |
| Fifth Floor  | 38              | 0          |

**COMMENTS:** New cables for conference area to go back to IDFG

## SPECIAL CABLING SCENARIOS

---

| Questions                                   | Yes/No | Quantity |
|---------------------------------------------|--------|----------|
| Are there any special cabling difficulties? | No     |          |
| Are new hatches required?                   | No     |          |
| Are plastic trunks required?                | No     |          |
| External cabling required                   | No     |          |
| Special access equipment                    | No     |          |
| Special tools required                      | No     |          |

**COMMENTS:** Ground floor conference area has multiple access hatches but is at 3.5 metres high, cable run through ceiling void.




## INSTALLATION CONSIDERATIONS


---



**COMMENTS:** Ground floor existing AP are inside the ceiling accessed by hatch and either on brackets or resting on top of the suspended ceiling.



**COMMENTS:** Existing Corridor AP's are cable tied onto waste pipes in risers.



**COMMENTS:** Each room has an RJ45 socket which is currently used for the IPTV, the MR36H AP bracket will fit in place of the RJ45 cover and the AP will mount without the need for any alteration to the TV mount.

## CABINETS, UPLINKS & SWITCH RECOMMENDATIONS

| PROPOSED NETWORK CABINETS |                         |              |             |                  |
|---------------------------|-------------------------|--------------|-------------|------------------|
| Cabinet                   | Location                | New/Existing | Dimensions  | Power outlets    |
| MDF                       | Ground Floor Comms Room | Existing     | 42U 800x800 | 3 x 12 3-pin PDU |
| IDFG                      | Ground Floor Comms Room | Existing     | 42U 800x800 | 1 x 12 3-pin PDU |
| IDF1                      | First Floor             | Existing     | 18U 600x600 | 1 x 6 3-pin PDU  |
| IDF2                      | Second Floor            | Existing     | 18U 600x600 | 1 x 6 3-pin PDU  |
| IDF3                      | Third Floor             | Existing     | 18U 600x600 | 1 x 6 3-pin PDU  |
| IDF4                      | Fourth Floor            | Existing     | 18U 600x600 | 1 x 6 3-pin PDU  |
| IDF5                      | Fifth Floor             | Existing     | 18U 600x600 | 1 x 6 3-pin PDU  |

**COMMENTS:** IDF's on floor 1-5 have no space in the rack to mount the new switches until the old switches are taken out.

| PROPOSED CABINET INTER-LINKS |                |              |                     |                  |
|------------------------------|----------------|--------------|---------------------|------------------|
| CABINET                      | REMOTE CABINET | NEW/EXISTING | LINK TYPE/INTERFACE | New/Spare/Re-use |
| MDF                          | IDFG           | Existing     | Fibre/1000          | Re-use           |
| MDF                          | IDF1           | Existing     | Fibre/1000          | Re-use           |
| MDF                          | IDF2           | Existing     | Fibre/1000          | Re-use           |
| MDF                          | IDF3           | Existing     | Fibre/1000          | Re-use           |
| MDF                          | IDF4           | Existing     | Fibre/1000          | Re-use           |
| MDF                          | IDF5           | Existing     | Fibre/1000          | Re-use           |

**COMMENTS:** Each IDF has 8 copper links and 4 fibre pairs, the fibre links are not currently in use. The fibre links should be tested to ensure they are functional.